

ASSISTED SERVICE CHILLED DELI -HYDROCARBON TYPE - R290 REFRIGERANT

- FITTING INSTRUCTIONS




General Installation Considerations

- 1) Area in which display is to be sited must have a minimum room floor area no less than 17 sq m (SCDL2ASHT & SCDL3ASHT), 20 sq m (SCDL4ASHT) or 28 sq m (SCDL5ASHT).
- 2) Install over a sealed floor or ventilated floor void.
- 3) Do not site the display within 2m of ceiling mounted air conditioning grilles. 6) Access to maintain condensing unit should be made via removable
- 4) Do not site the display beneath a high level of direct sunlight.
- 5) Display will operate in a 24 hour environment.
- fascia panels or doors to customer and operator side of counter.

A) WORKTOP CUT-OUT


Model Ref.	Worktop Cut Out Size (mm)		Model Weight
	Length	Width	(in Kg)
SCDL2ASHT	795	650	118
SCDL3ASHT	1145	650	140
SCDL4ASHT	1495	650	171
SCDL5ASHT	1845	650	204

FIX LIFTING BRACKETS TO FRAME END FLANGES USING SCREWS ALREADY IN FLANGES, THEN LOCATE LIFTING BARS INTO SQUARE HOLES.




FRONT ISOMETRIC

(CUSTOMER SIDE)




(CUSTOMER SIDE)




C) AIR OUTLET CUT-OUT

E) AIR INTAKE TUNNEL / PLENUM FITTING (CUSTOMER SIDE FASCIA PANEL)




A PLENUM OR 4 SIDED TUNNEL (MADE FROM MDF, PLYWOOD OR NILFLAM TYPE MATERIAL) MUST BE FITTED BETWEEN THE REAR FACE OF THE CUSTOMER SIDE FASCIA PANEL AND THE FRONT FACE OF THE COMPRESSOR CRADLE, AROUND THE AIR INTAKE CUT-OUT, TO STOP THE RE-CIRCULATION OF HOT AIR FROM THE COMPRESSOR. SILICON SEAL AROUND EDGES TO ENSURE THERE ARE NO AIR GAPS.

D) FITTING INTO COUNTER WORKTOP



F) FITTING OF LOUVRE GRILLES





Tel. 01254 238 282 Fax. 01254 238 228 e-mail: aftersales@cedlimited.com